MYSORE DIVISION.

Abstract Notification dated 23rd January 1936.

The attention of the public is invited to the detailed notification, calling for tenders for restoring Halehalli Hirikere Tank, Maddur Taluk, published on pages 134-135, Part VI of the *Mysore Gazette*.

The last date of receipt of tender is up to 2 P.M. on Monday the 17th February 1936.

Abstract Notification dated 23rd January 1936.

The attention of the public is invited to the detailed notification calling for tenders for improving Yelandur-Mamballi Road, published on page 135, Part VI of the *Mysore Gazette*. dated 30th January 1936.

The last date of receipt of tender is up to 10th February 1936.

Notification dated 3rd February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on Monday the 24th February 1936. for constructing two additional rooms in the rear of the Main building of the Middle School at Seringapatam. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 180 in cash or Government Promissory Notes, as earnest money, and be superscribed " tender for constructing two additional rooms to the Middle School Building at Seringapatam " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which, his tender will be considered cancelled. and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing two additional rooms in the rear of the main building of the Middle School at Seringapatam.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundations ..	C.yd.	0 3 0	31	6
2	Burnt brick in mud filling in foundations, basement and superstructure	C.ft.	0 3 6	3,179	695
3	Burnt brick in mortar sides of doors and windows	,,	0 4 6	367	103

No.	Item of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
4	Teakwood doors with panelled shutters 1″ to 1¼ thick with iron fittings complete ..	S.ft.	1 12 0	105	184
5	Teakwood windows, panelled shutters with iron fittings 1″ to 1¼″ thick	,,	2 0 0	189	378
6	Burnt stone slabs 6″ thick roughly dressed and fixed	,,	0 7 0	235	103
7	Teakwood work and put up with two coats of wood oiling	C.ft.	4 8 0	100·5	452
8	Providing Rolled Steel Girders including hoisting and painting	Cwt.	11 0 0	19·29	212
9	Pukka terrace complete with chunam plastering	Sqr.	33 0 0	8·84	292
10	Fixing new doors in place of windows at junction of old and new doors including dismantling masonry and repatching, etc.	No.	4 0 0	2	8
11	Removing old window in rear on either side of door and refixing in altered portion with repairs and dismantling and repatching, etc., complete	,,	3 0 0	2	6
11 (*a*)	Fixing old windows on New Masonry walls ..	,,	1 0 0	2	2
12	Chunam plastering	Sqr.	3 4 0	41·99	136
13	White washing	,,	0 4 0	53·39	13
14	Cornice with burnt brick in mortar 1¼′×5′ with plastering as per old design in plan ..	R.ft.	1 0 0	150	150
15	Ornamental parapet wall as per plan ⅜′—5′ with brick in mortar and plastering	R.ft.	1 12 0	136	238
16	Providing Ornamental finials as per plan 9′ high	No.	10 0 0	2	20
17	Flooring with 9″×9″ Mangalore Tiles over 3″ concrete bed including cement pointing ..	Sqr.	30 0 0	8·00	240
18	Chocolate painting 2 coats to doors and windows	,,	4 8 0	7·14	32
19	Dismantling masonry for inserting wall plates in old wall at junction and repatching work..	R.ft.	0 3 0	36	7
20	Clearing site, levelling ground, filling earth with the basement using bond slabs for old and new works and other sundry unforeseen works during execution of works	L.S.	..	..	25

Notification, dated 3rd February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M., on 24th February 1936 for Constructing Line Men's quarters at Honganahalli, 48th mile on Kankanhalli-Malavalli road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 125, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Line Men's quarters at Honganahalli, 48th mile on Kankanhalli-Malvalli road" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for Constructing Line Men's quarters at Honganahalli on 48th mile of Kankanhalli-Malvalli road.

No.	Items of work	Per	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation and filling in basement ..	C.yd.	0 3 0	33
2	Stone jelly concrete in chunam	C.ft.	0 3 6	288
3	Size stone in clay foundations and basement with bond stone at every 6′ apart	C.ft.	0 11 0	896
4	Superstructure, Burnt brick in clay	C.ft.	0 3 3	1,664
5	Burnt brick in mortar do	C.ft.	0 4 6	445
6	Burnt stone slabs 3″ thick roughly dressed and fixed in mortar	S.ft.	0 4 0	63
6(*a*)	Do 6″ thick do	S.ft.	0 6 0	109
7	Honney wood work wrought and put up with two coats of wood oiling	C.ft.	3 8 0	48·76
8	Honney wood doors with battened shutters 1″ thick including iron fittings, etc., complete ..	S.ft.	1 0 0	78
9	Honney wood battened windows 1″ thick shutters $\frac{5}{8}$″ iron bar complete with iron fittings	S.ft.	1 2 0	60
10	Roofing with 1st Class Mangalore tiles on teak reepers 1″ thick complete	Sqr.	27 0 0	13·47
11	Ridge tiles set in lime mortar and pointed	R.ft.	0 8 0	68
12	Providing and fixing ventilating tiles	Each	1 8 0	16
13	Honney wood almirahs complete with cross planks and front shutters	S.ft.	1 2 0	48
14	Binding wall over the roof 6″×6″ with chunam plaster..	S.ft.	0 4 0	28
15	Chunam plastering	Sqr.	3 4 0	45·84
16	White washing two coats	,,	0 4 0	45·84
17	Pointing with chunam mortar	,,	2 4 0	1·38
18	Flooring with 3″ Lime concrete with chunam plastering on top including cement rendering	,,	9 0 0	8·03
19	Providing sinks in rear bath room	Each	10 0 0	4
20	Do and fixing mortar and pestle stones ..	,,	4 0 0	4
21	Do Silk pattern drain along building with absorption pit, etc.	L.S.	..	..
22	Levelling ground and clearing site, etc.	L.S.	..	..
23	Sundry and unforeseen items during execution of work..	L.S.	..	..
24	Painting with two coats of Chocolate painting ..	Sqr.	3 0 0	4·00

V. V. PATANKAR,
Executive Engineer.